Calcium looping capture in the cement industry – CEMCAP Conclusions

G. Cinti[1], R. Matai[2], S. Becker[2], M. Alonso[3], C. Abanades[3], E. De Lena[4], M. Spinelli[4], M. Gatti[4], S. Campanari[4], S. Consonni[4], M. Romano[4], M. Hornberger[5], R. Spörl[5]

[1]Italcementi, Bergamo, Italy

[2]IKN GmbH, Neustadt, Germany

[3]Agencia Estatal Consejo Superior de Investigaciones Cientificas (CSIC), Madrid, Spain

[4]Politecnico di Milano, Milan, Italy

[5]Institute of Combustion and Power Plant Technology (IFK), University of Stuttgart, Stuttgart, Germany

2nd ECRA/CEMCAP/CLEANKER workshop:

Carbon Capture Technologies in the Cement Industry

Brussels, 17 October 2018

CEMCAP

Co-funded by the European Union

Calcium Looping process fundamentals

CO$_2$-lean flue gas

CO$_2$-rich gas to sequestration

CARBONATION

$CaO + CO_2 \rightarrow CaCO_3$

~ 650ºC

CALCINATION

$CaCO_3 \rightarrow CaO + CO_2$

~ 900ºC

CaCO$_3$

Heat

Heat

CaO (**F$_R$**)

Flue gas (CO$_2$) (**F$_{CO2}$**)

CaCO$_3$ make-up (**F$_0$**)

CaO purge

CEMCAP

Co-funded by the European Union

Calcium Looping for CO_2 capture: history

- Originally proposed by Shimizu et al., 1999. A twin fluid-bed reactor for removal of CO_2. Chem. Eng. Res. Des., 77.
- Continuously developed since 1998, mainly for application in power plants
- Several fluidized bed pilot facilities - demonstrated up to 1.7 MW

200 kW pilot at IFK, U. Stuttgart   *1 MW pilot at TU Darmstadt*   *1.7 MW pilot at La Pereda (ES)*

Calcium looping for cement plants

1. <u>Cement plant-power plant coupling</u>: CaO-rich spent sorbent from a CaL power plant as feed for the cement plant, as substitute of $CaCO_3$

   CEMCAP focus

2. <u>Post-combustion "tail end" configuration</u>: CaL process is integrated in the cement plant with a conventional post-combustion capture configuration

   CLEANKER focus

3. <u>Integrated CaL configuration</u>: the CaL process is integrated within the cement production process by sharing the same oxyfuel calciner

Calcium Looping CO_2 capture: Tail-end CaL configuration

General features of the process:

- Carbonator removes CO_2 from cement plant flue gas → Easy integration in existing cement

- Limestone partly calcined in Calcium Looping calciner → CaO-rich purge from CaL calciner used as feed for the cement kiln

- High fuel consumption (double calcination for the mineral CO_2 captured)

- Heat from fuel consumption recovered in efficient (~35% efficiency) steam cycle for power generation

- CFB CaL reactors: d_{50}=100-250 µm, vs. particle size for clinker production d_{50}=10-20 µm → CaL purge milled in the raw mill at low temperature


CEMCAP
Co-funded by the European Union

Calcium Looping CO_2 capture: Tail-end CaL configuration

Conducted Work:

- Parameter screening at 30 kW scale at CSIC (TRL5)

- Demonstration at semi-industrial scale (200 kW_{th}) at IFK (TRL6)

- Process integration study and techno-economic analysis

Arias et al., 2017. CO_2 Capture by CaL at Relevant Conditions for Cement Plants: Experimental Testing in a 30 kW Pilot Plant. *Ind. Eng. Chem. Res.*, 56, 2634–2640.

Hornberger et al., 2017. CaL for CO_2 Capture in Cement Plants – Pilot Scale Test. *Energy Procedia*, 114, 6171–6174.

Spinelli et al., 2017. Integration of CaL systems for CO_2 capture in cement plants. *Energy Procedia, 114, 6206-6214.*

De Lena et al., 2017. Process integration of tail-end CaL in cement plants. *Int J Greenh Gas Control. 67, 71-92.*

CEMCAP

Calcium Looping CO_2 capture: Tail-end CaL configuration

Demonstration at semi-industrial scale:

- High CO_2 capture up to 98 % demonstrated in TRL6 facility

- The CaL design parameters for cement plant applications are in good agreement with the design parameters for power plant operation.

- Tail-end CaL ready for demonstration at TRL7-8.

Calcium Looping CO_2 capture: integrated configuration

General information:

- CaL calciner coincides with the cement kiln pre-calciner

- Calcined raw meal as CO_2 sorbent in the carbonator

- Sorbent has small particle size (d_{50}=10-20 μm) → entrained flow reactors

Marchi M.I., et al., 2012. Procedimento migliorato per la produzione di clinker di cemento e relativo apparato. *Patents MI2012 A00382 and MI2012 A00382.*

Romano et al., 2014. The calcium looping process for low CO_2 emission cement plants. *Energy Procedia, 61, 500-503.*

# Calcium Looping CO_2 capture: integrated configuration

<u>Development of integrated CaL concept using entrained flow calciner/carbonator:</u>

- 1D carbonator modelling showed possibility of achieving high capture efficiency with solids/gas ratio of ~10 kg/Nm^3.

- Belite formation in calciner may cause a decrease of the sorbent CO_2 carrying capacity.

- Demonstration of chemistry and fluid-dynamics of the reactors in industrially relevant conditions needed.

Alonso et al., 2018. Capacities of Cement Raw Meals in Calcium Looping Systems. *Energy & Fuels*, 31, 13955–13962.

Spinelli et al., 2018. One-dimensional model of entrained-flow carbonator for CO_2 capture in cement kilns by calcium looping process. *Chemical Engineering Science, 191, 100-114.*

H&M balance

	Cement plant w/o capture	Tail-end CaL (20% integration)	Tail-end CaL (50% integration)	Integrated CaL
Carbonator CO_2 capture efficiency [%]	--	88.8	90.0	82.0
Total fuel consumption [MJ_{LHV}/t_{clk}]	3240	8720	7100	5440
Rotary kiln fuel consumption [MJ_{LHV}/t_{clk}]	1230	1220	1220	1150
Pre-calciner fuel consumpt. [MJ_{LHV}/t_{clk}]	2010	1550	850	4290
CaL calciner fuel consumpt. [MJ_{LHV}/t_{clk}]	--	5950	5040	
Net electricity consumpt. [kWh_{el}/t_{cem}]	97	-81	42	117
Direct CO_2 emissions [kg_{CO2}/t_{clk}]	865	119	79	55
Indirect CO_2 emissions [kg_{CO2}/t_{clk}] *	35	-29	15	46
Equivalent CO_2 emissions [kg_{CO2}/t_{clk}]	900	90	94	101
Equivalent CO_2 avoided [%]	--	90.0	89.5	88.8
SPECCA [MJ_{LHV}/kg_{CO2}] **	--	4.42	4.07	3.16

Evaluated with the average EU-28 electricity mix: η_e = 45.9%, $E_{CO2,e}$ = 262 kg/MWh

** *Specific primary energy consumption for CO_2 avoided*

De Lena et al., 2017. Process integration of tail-end CaL in cement plants. *Int J Greenh Gas Control. 67, 71-92.*

Economic analysis

Cost of CO_2 avoided = 50-55 €/t$_{CO2}$, mainly associated to Capex.

Conclusions and Outlook

Ca-LOOPING PROCESS INTEGRATION OPTIONS:

1. Post-combustion capture configuration:
   - Low uncertainty in the technical feasibility ✅
   - Very high CO_2 capture expected ✅
   - Two calciners are present in the system, leading to high fuel consumptions ❌

2. Integrated CaL configuration:
   - High CO_2 capture efficiency without modifying rotary kiln operation (no need of kiln oxyfiring). ✅
   - Higher thermal efficiency and lower fuel consumptions ✅
   - New carbonator design and fluid-dynamic regime: fluid-dynamics, heat management and sorbent performance need validation ❌

   – Competitive cost of CO_2 avoided. ✅

Calcium Looping
for cement industry
decarbonization
CLEANKER

CEMCAP