



Compaction by centrifugation is a technique typically limited to  $\phi 1-2m$ , arguably applicable to a  $\phi 13 m$  of the tower. Plus, spinning the 200-m long structure, if at all possible, results in unprecedented up-scaling in terms of equipment and energy and presents unreasonable execution risk (many spinning devices perfectly synchronized). Centrifuging discrete segments is the only realistic option but results in a non-monolithic structure.



Based on adaptation of pipe-jacking techniques. Instead of using hydraulic jacks to push prefabricated concrete segments into the soil, a circular arrangement of jacks will 'launch' previously filled molds into a reception lane. A new set of forms are then interlocked with the previous, filled with fresh concrete and launched again. All concreting operations are located at a fixed location

Comparable to slipforming in the sense that concrete is introduced axially, perpendicular to the cross-section of the tower into previously erected forms. The fundamental difference is how concrete is placed, linked to the fact that the device moves horizontally instead of vertically.



Tolerating a certain number of joints may result in a cheaper construction process. The cost reduction in construction by allowing joints in a segment approach will need to be compared to the costs of high-quality sealing of these joints, the increased maintenance costs and the impact on the life-time of the structure.

- ✓ High quality of centrifuge concrete
- ✓ High-production speed
- ✓ No need of inner core
- ✗ Non-monolithic
- ✗ High energy requirements to spin
- ✗ Increase of maintenance due to the presence of joints.

A Gantt Diagram is shown corresponding to the 3 first cycles of 5 identical stations with  $t_{lag} = 15$  min and  $t_{production} = 60$  min. After 270 min the total number of rings produced is  $5 \times 3 = 15$  rings. When Station No. 5 completes its first ring (min. 120) Station No. 1 is close to completing its second ring, (min 135). From that point on stations can connect rings for as long as required. As soon as a station has finished producing a ring it will re-start its operative cycle to fabricate another ring


Hydraulic jacks retracted to make room for cranes to assemble a new set of forms

Hydraulic jacks in pushing position 'extrude' the cross-section

Forms must interlock so action force of jacks can be transmitted throughout the system.

Pumping rate should be more intensive at the lower part to create a concrete slope within forms so concrete placed at higher levels has a base to fall on. Slope angle must be such that freshly pumped concrete does not slide off. Pumphines must be extendable and can rest on reinforcement bars not yet reached by concrete. New forms must be in place before the previous are completely filled whilst pouring never stops. The device slides backwards as construction progresses.

- ✓ Create value through new technology
- ✓ Highly automated
- ✗ Uncertain outcome
- ✗ Unproven and requires research
- ✗ Horizontal placement is difficult and slow



As long as  $t_{waiting} \ll t_{setting}$  concrete joints between rings will not form. To ensure bonding, extra concrete can be pumped radially at the interphase of a completed ring while waiting for the next ring to be connected. Train-like bogies and rail tracks allow swift transport of freshly filled molds.

- ✓ High-production speed
- ✗ Risk of cold-joints occurring
- ✗ Very time-sensitive
- ✗ High execution risk

Forms are equipped with 4 sets of wheels matching rails on reception lane.

- ✓ High-production speed
- ✓ Use experience from pipe jacking
- ✗ High-jacking forces on form panels
- ✗ Loads exerted on panels lead to buckling and early replacement of forms

Forms equipped with wheels

reception lane (with 4 rails)

self-propelled carriage

The giant re-usable mold, in which the bottom half is fixed and spans the entire length of the structure while the top half are a series of removable arch-forms. This method allows simultaneous pouring of the whole structure with directly discharging dumpster trucks and other high-throughput placement systems.

- ✓ High throughput
- ✓ Technological simplicity
- ✓ Low execution risk
- ✗ Large up-front costs to manufacture massive mold
- ✗ Permanency of facilities

